

DATE 7-12-62

SH. 1 OF 2

*[Handwritten signature]*

TMC SPECIFICATION NO. S - 10080

COMPILED BY  
A. Hawkins/hh

TITLE: TEST LIMITS FOR TRANSFORMER TR160

JOB

APPROVED *[Handwritten initials]*

TEST LIMITS FOR TRANSFORMER

TR-160

T. M. C. (CANADA) LIMITED  
OTTAWA ONTARIO

*[Handwritten mark]*

DATE 7-12-62  
SH. 2 OF 2

# TMC SPECIFICATION NO. S - 10080

COMPILED BY  
A. Hawkins/hh

TITLE: TEST LIMITS FOR TRANSFORMER

JOB

APPROVED

- 1.) Check for shorts with Ohmmeter before and after potting.

2.)

FREQUENCY	V <sub>1</sub>	V <sub>2</sub>	V <sub>3</sub>
2 Mc/s	1.0	.50 ± .05	.35 ± .05
4 Mc/s	1.0	.50 ± .05	.35 ± .05
6 Mc/s	1.0	.50 ± .05	.35 ± .05
8 Mc/s	1.0	.50 ± .05	.35 ± .05
16 Mc/s	1.0	.50 ± .05	.35 ± .05

