#### RECORD OF CORRECTIONS MADE

Change No.	Date of Change	Date Entered	Entered By
1	Superseded by Char	nge No. 2	
· <del>····································</del>			
		·	
•			
····			
·			
<del> </del>			
<del> </del>			
-			
•		·	
· · · · · · · · · · · · · · · · · · ·			
<del> </del>			
	_1	1	

CHANGE NO.	2
------------	---

#### INSTRUCTION BOOK CHANGE NOTICE

		Date	August	1972
Manual affected:	Sideband Multi-Channel	Exciter Model	SME-6	2045

Page 1-1, Section 1-1, second para

Line 5: Change "the CW" to "a"

Line 7: Delete "nine"

Page 1-2, Section 1-3,

Under Technical Specification AUDIO RESPONSE: Change all "2db" to "±1.5db".

Page 2-1, Section 2-2,

Line 6: Change "7-10" to "7-9".

Page 4-2, Section 4-2 d,

Delete the first paragraph in entirety, and replace with the following:

d. FREQUENCY SHIFT GENERATOR Z107. The frequency shift generator operates in the frequency shift keying (FSK) and facsimile (FAX) modes; it contains a 4.416 MHz oscillator section, a mixer section (utilizing the 3.0 MHz input from the power supply and the 4.416 MHz to provide 1.4166 MHz), and a 1.4166 MHz amplifier section, a keying modulator and dc amplifier section, and the FAX circuit. FSK operation is controlled by the SHIFT and FS LOOP switches.

In the second paragraph,

Line 13: Change "1.4166 MHz to "3.0 MHz".

Delete the third paragraph in entirety, and replace with the following:

When FSK or FAX operation is selected +12 vdc is supplied to both the

frequency shift generator and to the VXCO in the power supply assembly. As

a result the VXCO operates at the center frequency of 3.0 MHz. Upon application of the variable dc level (E MOD) from the SHIFT switch, the frequency

of the VXCO is shifted above and below center frequency, corresponding to

respective marks and spaces, by an amount determined by SHIFT switch setting

(±53, ±106, ±212, ±425). The frequency-shifted VXCO signal of 3.0 MHz is reapplied to the mixer section which provides a 1.4166 MHz signal ± the shift to the 1.4166 MHz amplifier section of the frequency shift generator and then to the converter and ALDC circuit, Z103.

Page 4-2, Section 4-2 f, second para,

Line 6: Change "incoming" to "output"

At end of para: Add "(Refer to Table 4-1)."

Page 4-3/4-4, Figure 4-1,

Change line from Power Supply Assembly marked "1.4166 MHz VXCO" to read "3.0 MHz VXCO."

Page 4-10, Section 4-3, para d. (4),

Delete this paragraph in entirety, and replace with the following:

(4) In the FSK and FAX modes of operation, the 3.0 MHz variable crystal-controlled oscillator (VXCO) is enabled in the power supply assembly, and its frequency is varied by the dc current produced in the FSK and FAX circuits of the frequency shift generator Z107. This in turn causes the same frequency variation in the 1.4166 MHz output of Z107. Since both the 250 kHz and 1.666 MHz inputs are inhibited in these modes, the 1.4166 MHz FSK-FAX input is coupled via jack J103 pin 8 and capacitor C4 to the input of 1.417 MHz amplifier Q2, thus bypassing 1.666 MHz amplifier Q1 and the balanced modulator circuit.

Page 4-10, Section 4-3, para f.

Delete thru line 8 of subparagraph (1), and replace with the following:

(1) Both FSK and FAX operation is initiated when MODE switch S102D (front) is set to either the FSK or FAX position as previously indicated in the discussion of MODE switching. In either of these positions S102D supplies a +12 vdc enable to both the 3.0 MHz crystal voltage controlled oscillator Z302 in the power supply assembly, and to the oscillator mixer in frequency-shift generator Z107. With the MODE switch in either the FSK or FAX positions, the 3.0 MHz VXCO input is applied to Z107 at pin M, and the 4.416 MHz oscillator on Z107 is enabled. Thes two signals are mixed, and their resultant signal (1.4166 MHz) is applied to the 1.4166 MHz buffer-amplifier section.

Page 4-12, Section 4-3, para f,

On the fifth line from top of the page, Change "1.4166 MHz" to "3.0 MHz"

Page 4-12, Section 4-3, paragraph f(2),

Delete paragraph f(2) in entirety, and replace with the following:

(2) With +12 vdc applied to 3.0 MHz oscillator Z302, and with the variable dc input present, respresenting keyer frequency shift, the frequency of Z302 varies about the 3.0 MHz center frequency by an amount dictated by SHIFT switch S110. The shifted frequency is appled to the oscillator/mixer section, whose 1.4166 MHz output is also shifted. This shifted frequency is then applied to the buffer-amplifier section of frequency shift generator Z107. The input signal, pin M of jack J107, is amplified in buffer Q1, and applied to limiter Z1 which maintains amplitude within acceptable limits without destroying the frequency shift characteristics. The limited output is applied to emitter follower Q2 and then through 1.4166 MHz Level Adjust potentiometer R16 via pin H of jack J107 to converter and ALDC circuit Z103.

Page 4-12, Section 4-3 g(2),

Line 15 and 16: Delete "odd or even"

Line 18: Change "incoming" to "output" and "five odd or five even" to "ten"

Delete last sentence

Table 4-1: Delete information in table and substitute the following Table:

TABLE	4-1.	RF OUT	FREQU	JENCY C	HANNELS
Channe	e1	Free	quency	Chann	els
1		1.0	5 to	2.099	9 MHz
2		2.	L to	2.799	9 MHz
3		2.8	3 to	3.799	9 MHz
4		3.8	3 to	5.099	9 MHz
5		5.3	l to	6.999	9 MHz
6		7.0	) to	8.999	9 MHz
7		9.0	) to	11.999	9 MHz
8		12.0	) to	15.999	9 MHz
9		16.0	) to	21.999	9 MHz
10		22.0	) to	30.999	9 MHz

Page 5-5, Table 5-2,

Under Step 6, "No FSK operation" and Step 7, change all references to "1.4166 MHz" to read "3.0 MHz"

Page 5-8, Section 5-3, i (3)

Change sentence after note to read as follows:

The oscillator frequency is a seven or eight digit number; for example:

Change example to the following:

(2) 17.783667 MHz Osc

1.416667 MHz IF

16.367000 MHz Output

Page 5-9, Section 5-3, j

Delete Section 5-3, j in entirety, and replace with the following:

- j. FREQUENCY SHIFT GENERATOR/OSCILLATOR-MIXER Z107. (See figure 5-6.) Perform the alignment of the frequency shift generator/oscillator-mixer as follows:
- (1) Connect the frequency counter to the vertical output terminals of the oscilloscope. Set the MODE switch to the FSK position and the EXCITER switch to the ON position. On the rear panel of the SME-6, set potentiometer R101 to mid-range, SHIFT switch to ±425 Hz (maximum shift position), SENSE switch to the (+) position, and S111 to the CONT. position.

#### NOTE

FSK adjustments must be made after the 3.0 MHz oscillator oven has warmed up for at least an hour.

- (2) Set R22 and R23 on Z107 fully counterclockwise.
- (3) Connect the oscilloscope to J107-M, and adjust R25 for a reading of 3.000000 MHz on the frequency counter.
  - (4) Mount the Z107 assembly on the extender board.
- (5) Connect the oscilloscope to J105-H, and adjust potentiometer R16 for maximum signal output level on the oscilloscope and C20 for a frequency reading of 1.41666 MHz on the counter.
  - (6) Return the Z107 assembly to the proper chassis socket.
- (7) With the oscilloscope connected to J105, adjust R25 (if required) for a frequency reading of 1.41666 MHz on the counter.

#### CHANGE NO. 2 (continued)

- (8) Adjust potentiometer R23 for a frequency of 1.416241 MHz on the counter. Set the SENSE switch to the (-) position and adjust potentiometer R22 for a frequency reading of 1.417091 MHz on the counter.
  - (9) Repeat step (8) until the frequencies are within 5 Hz.
- (10) Set the SHIFT switch to the  $\pm 212$  Hz position and the SENSE switch to the (+) position. The frequency counter should read 1.416878 MHz  $\pm 15$  Hz.
- (11) Repeat step (10) for the  $\pm 106$  Hz SENSE switch position and for the  $\pm 53$  Hz position. The tolerance is  $\pm 7$  Hz for the  $\pm 53$  Hz position.
  - (12) Mount the Z107 assembly on the extender board.
- (13) Connect the oscilloscope to J103-A and set the MODE switch to the CW position. Observe the peak-to-peak amplitude on the oscilloscope. Set the MODE switch to the FSK position, and adjust R16 on Z107 for the same peak-to-peak amplitude displayed in the CW mode.
- (14) Place MODE switch in FAX position and set potentiometer R28 fully cw.
- (15) Apply 0-10 volts power supply to FAX terminals on rear panel and set for 1.0 volt input.
- (16) Adjust potentiometer R29 for 1,416,266  $\pm 5$  Hz reading on the counter.
- (17) Reset input to 10.0 volts and adjust potentiometer R28 for  $1,417,066 \pm 5$  Hz reading on counter.
  - (18) Repeat steps (15) through (17).
- (19) Check for linearity by varying input from 1.0 to 10.0 volts Counter should change  $89 \pm 5$  Hz for every 1.0 volt change from 1.0 to 10.0 volts shown in Table 5-3.

Page 5-11, Figure 5-8,

Change "Z101" to "Z104", on the figure title.

Change the reference designation for the resistor located just above R73 from "R74" to "R88".

Change the reference designation for the resistor located to the left of T6 from "R50" to "R87".

Add the reference symbol for C52 just above and perpendicular to R69. Page 5-11, Figure 5-9,

Change the reference designation for the resistor located to the right of Z1 from "R118" to "R25".

Page 5-11, Figure 5-9, continued

Change the reference designation for the variable capacitor located in the lower right hand corner of the board from "C57" to "C37".

Change emitter orientation tab on Q19 from upper left hand to upper right hand.

Reverse the polarity symbol for CR4.

Change transformer orientation dot for T3 from right handside of T3 to left hand side.

Page 5-12,

Delete page 5-12 in entirety, and replace with new page 5-12 provided with this change.

Page 5-13, Figure 5-12,

Add reference symbol for R35 parallel to and between R26 and C25.

Add reference symbol for C32 parallel to and to the right of R32.

Add reference symbol for C33 parallel to R33 and to the right of Q6.

Add reference symbol for R34 parallel to and just above C26.

Show existing variable symbol for R27 in broken line form and add fixed resistor symbol for R27. In reference to this, add the following note:

If a variable R27 is used, the fixed R27 and R34 symbols should be deleted.

Change the reference designation for the capacitor located to the right of L1 from "C29" to "C34".

Page 5-13, Figure 5-13,

Delete the reference symbol for "R38" and add a jumper in its place.

Change the reference symbol "L3" to "R72".

Change the reference symbol "L9" to "R73".

Add reference symbol for R70 parallel to and just above R63.

Add reference symbol for R71 parallel to R67 and above Q11.

Add reference symbol for C62 perpendicular to R41 and to the left of Z3. Page 5-14, Figure 5-14,

Delete in entirety the Component Location drawing for Z115 and replace it with the drawing provided with this change.

Page 5-15/5-16, Figure 5-16,

Delete in entirety the reference symbol for R15.

Section 6, Parts List,

Delete Section 6 in entirety, and replace with new Section 6 provided with this change.

Page 7-1/7-2, Table 7-1,

Change TMC Drawing Number for Figure 7-5 from "CK1484" to "CK1920".

Change TMC Drawing Number for Figure 7-9 from "CK1328" to "CK1330".

Change TMC Drawing Number for Figure 7-10 from "CK1491" to "CK1328".

Page 7-3/7-4 and 7-5/7-6, Figure 7-1,

Delete Figure 7-1 in entirety, and replace it with the new figure provided with this change.

Page 7-7/7-8, Figure 7-2,

Correct the spelling of the title: "Gernerator" to "Generator".

Change the reference designation of the 33K resistor at the base of Q12 from "R88" to "R74".

On Last Symbol chart, change R87 to R88.

Add to Missing Symbol chart, "R43 thru R47, R50, R67".

Page 7-9/7-10, Figure 7-3,

Change the value of the following capacitors from "5, 25V" to "6.8,25V": C7, C10, C13, C14, C38, C61, C62, C65, C68, C72, C73, C80, C81.

Change the value of C70 from "4, 35V" to "6.8, 35V".

Change the value of the following capacitors from "10, 15V" to "10, 25V": C4, C6, C9, C11 and C71.

On Missing Symbols chart, delete "R36".

Page 7-13/7-14, Figure 7-5,

Delete in entirety the Schematic Diagram for Z107, and replace it with the Schematic provided with this change.

Page 7-15/7-16, Figure 7-6,

Change the value of R13 fron "100K" to "47K".

Change the value of Rl1 from "27K" to "10K".

In Last Symbol chart change "C31" to "C34" and "R34" to "R35".

Add symbol for R35, 1K in parallel with C25 and T4 primary.

Add symbol for C32, 0.1 between ground and the junction of R29, R30 and the base of Q5.

Add symbol for C33, 0.1 between ground and the junction of R32 and the base of Q6.

#### CHANGE NO. 2 (continued)

Page 7-15/7-16, Figure 7-6, continued

Add symbol for C34 between ground and the junction of pin 14 and L1. Page 7-17/7-18, Figure 7-7,

Change the value of the following capacitors from "4, 35V" to "6.8,35V": C21, C57.

To Missing Symbols chart, add "R38", "L3", and "L9".

On Last Symbol chart, change "C61" to "C62" and "R69" to "R73".

Delete in entirety "R38", the resistor between Z3 and C37.

Add the following:

to Z1 - "A0-125"

to Z2 - "A0-125"

to Z4, 8 - "TZ223"

to Z5,6,9,10 - "TZ225"

to Z7,11 - "TZ226"

Change the value of the following resistors from "22" ohms to "47" ohms:

R7, R13, R45, and R51

Change the value of the following resistors from "10" ohms to "22" ohms:

R18, R56

Delete the symbol for L3 in entirety, and add in its place the symbol for R72, 470 ohms.

Delete the symbol for L9 in entirety, and add in its place the symbol for R73, 470 ohms.

Add symbol for R70, 10 ohms in the base lead of Q4.

Add symbol for R71, 10 ohms in the base lead of Q11.

Add symbol for C62 between the ground on Z3 and the junction of R37 and the Z3 input terminal.

Page 7-19/7-20, Figure 7-8,


Change value of C2 from ".01" to "20uf, 50WV".

Change value of R4 from "2K" to "5K".

Page 7-19/7-20, Figure 7-8, continued

Add a capacitor symbol in broken line form between ground and the junction of CR1 and C31. Mark value of capacitor .01. Remove ground symbol from C31 symbol and add a resistor in series with C31 to ground. Mark resistor as R20, 100. Change value of C31 from .01 to "50, 15V", and add the following note:

Note: R20 deleted and C31 replaced by .01 to ground when exciter is used with HFLA-1K.



Page 7-21/7-22, Figure 7-9,

Delete Figure 7-9 in entirety, and replace with new drawing provided with this change.

Page 7-25/7-26, Figure 7-11,

Delete in entirety the resistor R15.

Add "R1915" to Missing Symbols chart.




Figure 5-10. AM Amplifier Z108, Component Location




Figure 5-11. Frequency Shift Generator Z107, Component Location




Figure 5-14. RF Output Z115, Component Location

# SECTION 6 PARTS LIST

#### 6-1. INTRODUCTION

The parts list presented in this section is a cross-reference list of parts identified by a reference designation and TMC part number. In most cases, parts appearing on schematic diagrams are assigned reference designations in accordance with MIL-STD-16. Wherever practicable, the reference designation is marked on the equipment, close to the part it identifies. In most cases, mechanical and electro-mechanical parts have TMC part numbers stamped on them.

To expedite delivery when ordering any part, specify the following:

- a. Reference symbol.
- b. Description as indicated in parts list.
- c. TMC part number.
- d. Model and serial numbers of the equipment containing the part being replaced; this can be obtained from the equipment nameplate.

For replacement parts not covered by warranty (refer to warranty sheet in front of manual), address all purchase orders to:

The Technical Materiel Corporation Attention: Sales Department 700 Fenimore Road Mamaroneck, New York

The following assemblies are standard in all configurations of the SME( )-6:

Assembly or Sub-Assembly:	Page
misiz, to board in (tower suppress), (2001)	6-2 6-8 6-16 6-20 6-25 6-28 6-29 6-30
The following additional assemblies are customer-specified options:  Assembly or Sub-Assembly:	Page
A4707, Sideband Generator, (Z105 and/or Z109)	6-32 6-41 6-43 6-46
A4647, Amplifier, (Additional channel capability; any or all of the following: Z102, Z111-113)	6-20

SME ( )-6

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C101	Cap, Fxd, Mica, 1000 uuf, +10%, 300 WVDC	CB21QB102K
thru	,	3321,631,1
C103		
C104	Cap, Fxd, Cer, 20,000 uuf, +80%-20%, 500 WVDC	CC100-24
C105	Same as C101	
thru		
C109		
C110	Same as C104	
C111	Same as C101	
C112	Cap, Dis, Cer, 10,000 uuf, +80%-20%, 25 WVDC	cc100-41
C113	Same as C101	
and		
C114		·
C115	Same as C112	
C116	Same as C101	
and		
C117		
C118	Same as C112	
C119	Same as C112	
C120 ·	Same as C112	
C121	Cap. Dis, Cer, 1000 uuf, GMV, 500 WVDC	CC100-29
C122	Same as C121	
C123	Same as C121	
C124	Same as C121	
C125	Same as C112	
C126	Same as C112	
C127	Same as C112	
C128	Same as C121	
C129	Same as C121	
C130	Same as C121	
C131	Same as C121	
C132	Same as C121	

SME()-6

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C132	Same as C121	
C133	Same as C112	
C134	Same as C121	
C135	Same as C121	
c136	Same as C121	
C137	Same as C121	
C138	Same as C112	
thru		
C149		
C150	Cap, Fxd, Mylar, 1.0 mfd, <u>+</u> 5%, 50 WVDC	CN114-1R0-5J
C151	Same as C112	
thru		
c160 ·		
C161	Same as C101	
C162	Same as C112	
CR101	semiconductor, Device, Diode	1N914
CR 102	Same as CR101	
DS101	Lamp, Incand, 28.0 volts, ac/dc, .04 amps	B1110-7
DS 102	Same as DS101	
F101	Fuse, Ctg, 1 amp at 115 volts or	FU102-1.00
	1/2 amp at 230 volts	FU102-0.50
F102	Same as F101	
J101	Conn, Recp, Fml, 30 double contacts	JJ319A15DFE
thru		
J105		
J106	NOT USED	
J107	Same as J101	
thru		
J109		·
J110	NOT USED	
JIII	Same as J101	İ
thru		
J113		

SME()-6

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
J114	NOT USED	
J115	Same as J101	
J116	Conn, Recp, Male, 3 contacts	MS3102A16S-5P
´J117	Jack, Tel, Key	JJ034
J118	Jack, Tel, Mike	JJ033
J119	Conn, Recp, Male	JJ333-104P-FS-4
J120	Conn, Recp, 1 female contact, 52 ohms, BNC type	UG625/U
J121	Same as J120	
J122	NOT USED	
J123	Same as J120	
thru		
J125		
К101	Relay, Arm, Min.	RL143-4
K102	Relay	RL156-5
L101	Coil, RF, Fixed, 120 uh, 315 ma,	CL 240-120
thru	·	
L104		
L105	Coil, Rf, Fixed, Ferrite Bead	CL 349-1
L106	Same as L105	·
L107	Same as L101	
.thru		
L109		
L110	NOT USED .	
LIII	Same as L101	
L112	NOT USED	
L113	Same as L101	
L114	Same as L101	
L115	NOT USED	
L116	Same as L101	
thru		
L118		
M101	Meter	MR191-9
R101	Res, Var, Comp, 1000 ohms <u>+</u> 10%, 1/2 watt	RV106UV8B102A

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R102	Res, Var, Comp, 100 ohms, $\pm 10\%$ , 2 watts	RV4NAYSD101A
R103	Res, Var, Comp, 500 ohms, <u>+</u> 20%, 2 watts	RV4NAYSD501A
R104	Same as R103	
R105	Res, Var, Comp, 25000 ohms $\pm 10\%$ , 2 watts	RV4NAYSD253A
R106	Res, Var, Comp, 1000 ohms, +10%	RV110-1
R107A,B	Res, Var, Comp, Panel Section 1K ohm Log	RV108-2
	Rear Section 10K ohm Linear	
R108	Res, Fxd, Comp, 680 ohms $\pm 5\%$ , $1/4$ watt	RC07GF681J
R109	Res, Fxd, Comp, 220 ohms, <u>+</u> 5%, 1/4 watt	RC07GF221J
R110	Same as R109	
R111	Res, Fxd, Comp, 2200 ohms, <u>+</u> 5%, 1/4 watt	RC07GF222J
R112	Res, Fxd, Comp. 390 ohms, <u>+</u> 5%, 1/4 watt	RC07GF391J
R113	Res, Fxd, WW, 1 ohm, <u>+</u> 0.5%	RW126-4-1R0
R114	Same as R113	·
R115	Res, Fxd, Comp. 47000 ohms, $\pm 5\%$ , 1/4 watt	RCO7GF473J
R116	Same as R115	
R117	Res, Fxd, Comp, 1000 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF102J
R118	Same as R117	
R119	Same as R117	
R120	Res, Fxd, Comp, 3900 ohms, <u>+</u> 5%, 1/4 Watt	RCO7GF392J
R121	Res, Fxd, Comp, 56000 ohms, <u>+5</u> %, 1/4 watt	RCO7GF563J
R122	Res, Fxd, Comp, 27000 ohms, $\pm 5\%$ , 1/4 watt	RCO7GF273J
R123	Res, Fxd, Comp, 1500 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF152J
R124	Res, Fxd, Comp, 150 ohms, <u>+</u> 5%, 1/4 watt	RC42GF151J
R125	Same as R124	110 1201 1310
R126	Res, Fxd, Comp, 5600 ohms <u>+</u> 5%, 1/4 watt	RCO7GF562J
R127	Res, Fxd, Comp, 8200 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF822J
R128	Res, Fxd, Comp, 10000 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF103J
R129	Same as R117	
R130	Same as R117	
R131	Same as R128	
thru		
R133		

SME( )-6

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R134	Same as R117	
thru		
R137		
R138	Same as R109	
R139	Res, Fxd, Comp, 2200 ohms, <u>+</u> 5%, 1/2 watt	RC20GF222J
R140	Same as R139	
R141	Res, Fxd, Comp, 470 ohms, <u>+5</u> %, 1/2 watt.	RC20GF471J
R142	Res, Var, Comp, 10000 ohms, +10%, 2 watt	RV106UX8B103A
R143	Res, Fxd, Comp, 330000 ohms, +5%, 1/4 watt	RCO7GF334J
R144	Same as R113	100,000
R145	Res, Fxd, Comp, 47 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF470J
R146	Res, Fxd, Comp, 100 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF101J
R147 ·	Same as R146	
S101	Sw, Rotary, Channel	SW473
\$102	Sw, Rotary, Mode	SW475
S103	Sw, Rotary, Carrier Suppression	SW474
S104	Sw, Rotary, Meter	SW476
S105	Sw, Toggle, DPDT	ST22N
S106	. Same as S105	
S107	NOT USED	
S108	NOT USED	
S109	Sw, Toggle, SPDT	ST103-11-62
S110	Sw, Rotary, Shift	SW447
S111	Sw, Rotary, Loop	sw446
TB101	NOT USED	
TB102	NOT USED	
TB103	Term, Bd, Barrier	TM100-6
TB104	Same as TB103	
TB105	Term, Bd, Barrier	TM100-8
Z101	RF, Amp, Assy	A-4647
and		
Z 102		
Z103	Converter/ALDC Assy	A-4717

SME()-6.

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
Z104	Carrier Generator Assy	A-4656
Z105	Upper Sideband Generator Assy	A-4707-1
Z106	NOT USED	
Z107	FS Generator Assy	A-4905 ε
		A-4906
Z108	AM Amplifier Assy	A-4718
Z109	Lower Sideband Generator Assy	A-4707-2
Z110	NOT USED	
Z111	Same as Z101	
thru		
Z113		
Z114	NOT USED	
Z115 ·	RF Output Assy	A-4502
	•	
	·	

## A4656 🗸

REF SYMBOL	DESCRIPTION	. TMC PART NUMBER
C1	Cap, Disc, Cer, 100,000 uuf, +80-20%, 25 WVDC	CC100-44
C2	Cap, Disc, Cer, 10000 uuf, +80-20%, 500 WVDC	CC100-16
C3 thru C5	Same as C2	
C6	Cap, Fxd, Mica, 2700 uuf, +1%, 500 WVDC	CM112F272F5S
C7	Cap, Fxd, Mica, 680 uuf, +1%, 300 WVDC	CM111F681J3S
C8	Cap, Fxd, Mica, 3900 uuf, +1%, 300 WVDC	CM112F392G3S
C9	Cap, Fxd, Mica, 1300 uuf, +1%, 500 WVDC	CM112F132F5S
C10	Cap, Fxd, Mica, 3600 uuf, <u>+</u> 1%, 500 WVDC	CM112F362G5S
C11 and C12	Same as Cl	
C13	Same as C8	
C14 thru C16	Same as Cl	
C17	Same as C8	
C18 thru C20	Same as C1	
C21	Same as C2	
C22 thru C26	Same as C1	,
C27	Cap, Elec, 10 ufd, 25 WVDC	CE105-10-25
C28	Same as C1	
C29	Same as C2	
C30	Cap, Fxd, Mica, 300 uuf, <u>+</u> 5%, 500 WVDC	CM111E301J5S

RE F SYMBOL	DESCRIPTION	TMC PART NUMBER
C31	Same as C2	
C32	Cap, Fxd, Mica, 15 uuf, +5%, 500 WVDC	CM111C150J5S
C33	Same as C30	
C34 and	Same as C2	
C35		
C36	Same as C30	
C37	Same as C2	
C38	Same as C32	
C39	Same as C30	
C40	Same as Cl	
C41	Same as C30	
C42	Same as C2	
C43	Same as C2	
C44	Cap, Disc, Cer, 1000 uuf, +80-20%,	CC100-29
C45 thru	Same as Cl	
C47		
C48	Cap, Fxd, Mica, 470 uuf. <u>+</u> 1%, 500 WVDC	CM111F471F5S
C49	Cap, Fxd, Mica, 51 uuf, <u>+</u> 2%, 500 WVDC	CM111E510G5S
C50	Same as C7	
C51	Cap, Fxd, Mica, 82 uuf, +1%, 500 WVDC	CM111E820F5S
C52	Cap, Fxd, Mica, 600 uuf, <u>+</u> 5%, 300 WVDC	CM111F601J3S
C53	Same as C2	
thru C56		
C57	Cap, Fxd, Mica, 910 uuf, <u>+</u> 5%, 100 WVDC	CM111F911J1S
C58	Same as C2	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C59	Same as C49	
C60	same as C57	
C61 and C62	Same as C2	
C63	Cap, Fxd, Mica, 1000 uuf, +1%, 100 WVDC	CM111F102F1S
C64 thru C66	Same as C2	
C67	Same as Cl	
C68	Same as C27	
C69	Same as C27	
C70	Cap, Elec, 150 ufd, 15 WVDC	CE105-150-15
C71	Same as C2	
C72	Cap, Elec, 2 mfd, 50 WVDC	CE105-2-50
C73	Same as C72	
C74	Same as Cl	
C75	Same as C2	
C76	Same as Cl	
CR1	Diode, Ref, Silicon	1N751
CR2	Diode, Silicon, Computor Diode	1N914
CR3	Same as CR1	
CR4	Diode, GE, Silicon	1N34A
L1	Coil, 1,000 uh, +10%, 135 ma	CL275-102
ĽŽ	Coil, 180 uh, <u>+</u> 10%, 260 ma	CL275-181
L3	Same as L2	

A4656

L4 Coil, 1500 uh, ±10%, 275 ma CL275-151  L5 thru L7  L8 Coil, 33 uh, ±10%, 505 ma, CL275-330  L9 Same as L8  L10 Coil, 22 uh, ±10%, 565 ma CL275-220  L11 and L12  L13 Coil, 220 uh, ±10%, 250 ma CL275-221  L14 Same as L1  Q1 Transistor, Silicon, Epox 2N3646  Q2 thru Q14  R1 Res, Fxd, Comp, 470 ohms, ±5%, 1/4 watt RC07GF471J  R2 Res, Fxd, Comp, 47 ohms, ±5%, 1/4 watt RC07GF470J  R3 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt RC07GF104J  R4 Same as R3  R5 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt RC07GF103J  R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt RC07GF222J  R7 Res, Fxd, Comp, 3900 ohms, ±5%, 1/4 watt RC07GF392J	REF SYMBOL	DESCRIPTION	TMC PART NUMBER
thru L7  L8	L4	Coil, 1500 uh, <u>+</u> 10%, 275 ma	CL275-151
L9 Same as L8  L10 Coil, 22 uh, ±10%, 565 ma  CL275-220  L11 and L12  L13 Coil, 220 uh, ±10%, 250 ma  CL275-221  L14 Same as L1  Q1 Transistor, Silicon, Epox  Same as Q1  thru Q14  R1 Res, Fxd, Comp, 470 ohms, ±5%, 1/4 watt  R2 Res, Fxd, Comp, 47 ohms, ±5%, 1/4 watt  R3 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt  R4 Same as R3  R5 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt  RC07GF103J  R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt  RC07GF222J	thru	Same as L1	
L10	L8	Coil, 33 uh, <u>+</u> 10%, 505 ma,	CL275-330
L11 and L12  L13	L9	Same as L8	
and L12  L13	L10	Coil, 22 uh, <u>+</u> 10%, 565 ma	CL275-220
L14 Same as L1  Q1 Transistor, Silicon, Epox  2N3646  Q2 thru Q14  R1 Res, Fxd, Comp, 470 ohms, ±5%, 1/4 watt  R2 Res, Fxd, Comp, 47 ohms, ±5%, 1/4 watt  R3 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt  R4 Same as R3  R5 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt  R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt  RC07GF103J  R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt  RC07GF222J	and	Same as L1	
Q1 Transistor, Silicon, Epox  Q2 thru Q14  R1 Res, Fxd, Comp, 470 ohms, ±5%, 1/4 watt  R2 Res, Fxd, Comp, 47 ohms, ±5%, 1/4 watt  R3 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt  R4 Same as R3  R5 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt  R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt  R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt  R707GF103J  R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt  R707GF222J	L13 .	Coil, 220 uh, <u>+</u> 10%, 250 ma	CL275-221
Q2 thru Q14  R1 Res, Fxd, Comp, 470 ohms, ±5%, 1/4 watt R2 Res, Fxd, Comp, 47 ohms, ±5%, 1/4 watt R3 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt R4 Same as R3  R5 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt RC07GF103J R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt RC07GF222J	<u>L14</u>	Same as L1	
thru Q14  R1 Res, Fxd, Comp, 470 ohms, ±5%, 1/4 watt RC07GF471J  R2 Res, Fxd, Comp, 47 ohms, ±5%, 1/4 watt RC07GF470J  R3 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt RC07GF104J  R4 Same as R3  R5 Res, Fxd, Comp, 10000 ohms, ±5%, 1/4 watt RC07GF103J  R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt RC07GF222J	Ql	Transistor, Silicon, Epox	2N3646
R2 Res, Fxd, Comp, 47 ohms, ±5%, 1/4 watt RC07GF470J R3 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt RC07GF104J R4 Same as R3 R5 Res, Fxd, Comp, 10000 ohms, ±5%, 1/4 watt RC07GF103J R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt RC07GF222J	thru	Same as Q1	
R3 Res, Fxd, Comp, 100000 ohms, ±5%, 1/4 watt R4 Same as R3 R5 Res, Fxd, Comp, 10000 ohms, ±5%, 1/4 watt R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt RC07GF103J R6 Res, Fxd, Comp, 2200 ohms, ±5%, 1/4 watt	R1	Res, Fxd, Comp, 470 ohms, +5%, 1/4 watt	RC07GF471J
R4 Same as R3  R5 Res, Fxd, Comp, 10000 ohms, <u>+</u> 5%, 1/4 watt  R6 Res, Fxd, Comp, 2200 ohms, <u>+</u> 5%, 1/4 watt  RC07GF103J	R2	Res, Fxd, Comp, 47 ohms, $\pm 5\%$ , $1/4$ watt	RC07GF470J
R5 Res, Fxd, Comp, 10000 ohms, <u>+</u> 5%, 1/4 watt RC07GF103J R6 Res, Fxd, Comp, 2200 ohms, <u>+</u> 5%, 1/4 watt RC07GF222J	R3	Res, Fxd, Comp, 100000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF104J
R6 Res, Fxd, Comp, 2200 ohms, <u>+5</u> %, 1/4 watt RC07GF222J	R4 .	Same as R3	
	R5	Res, Fxd, Comp, 10000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF103J
R7 Res, Fxd, Comp, 3900 ohms, ±5%, 1/4 watt RC07GF392J	R6	Res, Fxd, Comp, 2200 ohms, <u>+</u> 5%, 1/4 watt	RC07GF222J
	R7	Res, Fxd, Comp, 3900 ohms, +5%, 1/4 watt	RC07GF392J

A4656

RE F SYMBOL	DESCRIPTION	TMC PART NUMBER
R8	Same as R6	
R9_	Res, Fxd, Comp, 150 ohms, <u>+</u> 5%, 1/2 watt	RC20GF151J
R10	Same as R6	
R11	Res, Fxd, Comp, 220 ohms, <u>+</u> 5%, 1/4 watt	RC07GF221J
R12	Same as R5	
R13	Res, Fxd, Comp, 33000 ohms, +5%, 1/4 watt	RCO7GF333J
R14	Res, Fxd, Comp, 1,000 ohms, +5%, 1/4 watt	RC07GF102J
R15	Res, Fxd, Comp, 100 ohms, $\pm 5\%$ , 1/4 watt	RC07GF101J
R16	Same as R14	
R17 ·	Same as R15	
R18	Same as R13	
R19	Same as R5	
R20	Same as R14	
R21	Same as R15	
R22	Same as R14	
R23	Res, Var, 100 ohms, <u>+</u> 30%, 1/2 watt	RV124-1-101
R24	Res, Var, 500 ohms, <u>+</u> 30%, 1/2 watt	RV124-1-501
R25	Same as R5	
R26	Same as R7	
R27	Same as R24	
R28	Same as R14	
R29	Same as R14	
R30 R31 R32	Same as R14 Same as R1 Same as R2	
R33	Same as R13	

A4656

RE F SYMBOL	DESCRIPTION	TMC PART NUMBER
R34	Same as R5	
R35	Same as R14	
R36	Same as R14	
R37	Res, Fxd, Comp, 150 ohms, +5%, 1/4 watt	RC07GF151J
R38	Res, Fxd, Comp, 120 ohms, <u>+</u> 5%, 1/4 watt	RC07GF121J
R39	Same as R13	
R40 R41 R42 R43 thru R47 R48  R49 R50 R51  R52  R53  R54  R55  R56  R57  R58  R59 R60	Same as R5 Same as R14 Same as R2 NOT USED  Same as R37 NOT USED Same as R13 Same as R5 Same as R2 Same as R2 Same as R14 Same as R14 Same as R15 Same as R15 Same as R3 Same as R3 Same as R3	
R61	Same as R7	
R62	Same as R6	
R63	Same as R9	

RE F SYMBOL	DESCRIPTION	TMC PART NUMBER
R64	Same as R5	
R65	Same as R11	
R66 R67 R68	Same as R5 NOT USED Same as R14	
R69	Same as R15	
R70	Same as R14	
R71	Res, Fxd, Comp, 180 ohms, <u>+</u> 5%, 1/4 watt	RC07GF181J
R72	Same as R71	
R73	Same as R5	
R74	Same as R13	
R75	Same as Rl	
R76	Same as R15	
R77	Same as R1	
R78	Res, Fxd, Comp, 22000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF223J
R79	Res, Fxd, Comp, 6800 ohms, <u>+</u> 5%, 1/4 watt	RC07GF682J
R80	Res, Fxd, Comp, 1200 ohms, <u>+</u> 5%, 1/4 watt	RC07GF122J
R81	Res, Fxd, Comp, 68 ohms, <u>+</u> 5%, 1/4 watt	RC07GF680J
R82	Res, Fxd, Comp, 3300 ohms, <u>+</u> 5%, 1/4 watt	RC07GF332J
R83	Same as R15	
R84	Res, Fxd, Comp, 4700 ohms, $\pm 5\%$ , 1/4 watt	RC07GF472J
R85	Same as R5	
R86	Same as R5	
R87	Same as R38	
R88	Same as R13	

A4656

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
T1 .	Transformer RF, Tuned	TT285-12
Т2	Transformer RF, Tuned	TT285-11
<b>T</b> 3	Transformer RF, Tuned	TT296-6
Т4	Same as T3	
T5 thru T7	Same as T3	
Т8	Transformer RF, Tuned	TT296-4
Т9	Same as T8	
T10	Transformer, RF, Tuned	TT296-5
21	Dual, Flip, Flop	NW159
Z2	Same as Z1	
		·

# A4717 🖊

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C1	Cap, Fxd, Cer, 100,000 uuf, +80-20%, 25 WVDC	CC100-44
C2 and C3	Same as Cl	
C4	Cap, Fxd, Cer, 10000 uuf, +20-20%, 50 WVDC	CC100-42
C5	Cap, Fxd, Mica, 1000 uuf, +1%, 100 WVDC	CM111F102F1 <b>S</b>
C6 and C7	Same as C1	
C8 and C9	Cap, Fxd, Mica, 6800 uuf, <u>+</u> 2%, 500 WVDC	CM112F682G3S
C10	Same as C4	
C11	Same as C1	
C12	Cap, Fxd, Cer, 20000 uuf, +80-20%, 25 WVDC	CC100-40
C13	Same as Cl	
C14	Same as C4	
C15	Cap, Fxd, Cer, 750 uuf, +5%, 300 WVDC	CM111F751J3
C16 thru C18	Same as Cl	
C19	Cap, Fxd, Cer, 1000 uuf, +80-20%	CC100-29
C20	Same as Cl	
C21	Same as C15	
C22	Same as C4	
C23	Same as C1	
C24	Cap, Fxd, Cer, 100000 uuf, +80-20%, 100 WVDC	CC100-28
C25	Same as C15	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C26	Same as C1	
C27	Same as C24	
C28	Same as C24	
C29 and	Same as C1	
C30 C31 C32 C33 C34	Same as C4 Same as C24 Same as C24 Same as C1	
CR1	Diode	DD139
CR2	Same as CR1	
L1 thru L3	Coil, 1000 UH, <u>+</u> 20%, 135 ma	CL275-102
L4	Coil, 68 uuf, <u>+</u> 10%	CL275-680
L5 thru L7	Same as Ll	
L8	Coil, 120 uh, <u>+</u> 10%, 20 ma	CL275-121
L9	Coil, 2220 uh, <u>+</u> 10%, 250 ma	CL275-221
Q1	Transistor	2N3646
Q2 and Q3	Same as Q1	
Q4	Transistor	2N3295
Q5 thru Q7	Same as Q1	
<u>R1</u>	Res, Fxd, Comp, 22000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF223J
R2	Res, Fxd, Comp, 5600 ohms, <u>+</u> 5%, 1/4 watt	RC07GF562J
R3	Res, Fxd, Comp, 470 ohms, <u>+</u> 5%, 1/4 watt	RC07GF471J

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R4	Res, Fxd, Comp, 10 ohms, +5%, 1/4 watt	RCO7GF100J
R5	Res, Fxd, Comp, 1000 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF102J
R6	Res, Var, 500 ohms, <u>+</u> 30%	RV124-1-501
R7	Res, Fxd, Comp, 120 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF121J
R8	Res, Fxd, Comp, 10000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF103J
R9	Same as R5	
R10	Res, Fxd, Comp, 100 ohms, <u>+</u> 5%, 1/4 watt	RC07GF101J
R11	Same as R8	
R12	Res, Fxd, Comp, 22 ohms, 1/4 watt	RC07GF220J
R13	Res, Fxd, Comp, 47000 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF473J
R14	Same as R5	
R15	Res, Fxd, Comp, 180 ohms, <u>+</u> 5%, 1/4 watt	RC07GF181J
R16	Same as R4	
R17	Same as R5	
R18	Res, Fxd, Comp, 1500 ohms, $\pm 5\%$ , 1/4 watt	RC07GF152J
R19	Res, Fxd, Comp, 12000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF123J
R20	Res, Fxd, Comp, 2700 ohms, <u>+</u> 5%, 1/4 watt	RC07GF272J
R21	Same as R3	
R22	Res, Fxd, Comp, 220 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF221J
R23	Same as R22	
R24	Res, Fxd, Comp, 330 ohms, $\pm 5\%$ , 1/4 watt	RCO7GF331J
R25	Res, Fxd, Comp, 15000 ohms, $\pm 5\%$ , $1/4$ watt	RC07GF153J
R26	Res, Fxd, Comp, 27000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF273J
R27	Same as R6 when variable, or Res, Fxd, Comp, 27 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF270J
	1 100 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1

DESCRIPTION	TMC PART NUMBER
Same as R5	
Res, Fxd, Comp, 820000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF824J
Res, Fxd, Comp, 330000 ohms, +5%, 1/4 watt	RC07GF334J
Res, Fxd, Comp, 220000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF224J
Same as R8	
Res, Fxd, Comp, 4700 ohms, <u>+</u> 5%, 1/4 watt	RC07GF472J
Same as R22 Same as R5 Transformer, Var,	TT296-1
Transformer, Var	TT296-2
Transformer, Var	TT296-3
Filter Band Pass	FX286
·	
	Same as R5 Res, Fxd, Comp, 820000 ohms, ±5%, 1/4 watt Res, Fxd, Comp, 330000 ohms, ±5%, 1/4 watt Res, Fxd, Comp, 220000 ohms, ±5%, 1/4 watt Same as R8 Res, Fxd, Comp, 4700 ohms, ±5%, 1/4 watt Same as R22 Same as R5 Transformer, Var, Transformer, Var Filter Band Pass

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C1	Cap, Fxd, comp, 10000 PF, +20%, 100 WVDC	CC-100-43
C2 C3 C4 thru C6	Cap, Var, Glass, 1.0-52.0 PF, 1000 WVDC NOT USED Same as C1	CV116-2
C7 C8 C9 thru C13	Same as C2 NOT USED Same as C1	
C14	same as C2	
C15 thru C19	Same as C1	
C20	Same as C2	
C21	Cap, Fxd, Elec, 6.8 mfd, +50-20%, 35WVDC	CE122-6R8-35
C22 thru C37 C38 C39 C40 thru C42	Same as C1  NOT USED  Same as C2  Same as C1	
C43 C44 C45 thru C47	Same as C2 NOT USED Same as C1	
C48 C49	NOT USED Same as Cl	
C50	Same as C2	
C51 thru C55	Same as Cl	
C56	Same as C2	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C57	same as C21	
C58 thru C61	Same as Cl	
C62 CR1	Factory Selected Diode, Semiconductor Device, Voltage Regulator	IN759A
CR2	Diode, Semiconductor Device,	IN914
CR3	Same as CR2	
CR4	Same as CR1	
CR5	Same as CR2	
CR6	Same as CR2	
Ll	Coil, Radio Frequency, 120 uh, +20%, 20ma	CL275-121
L2	Same as Ll	
L3	NOT USED	
L4	Same as L1	
thru		
L8		
L9	NOT USED	
L10	Same as Ll	
Q1 Q2 Q3	Transistor Same as Q1 Same as Q1	2N3646
Q4 Q5 thru	Transistor Same as Q1	2N5179
Q11	Same as Q4	
R1	Res, Fxd, Comp, 470 ohms, + 5%, 1/2 watt	RC20GF471J
R2	Res, Fxd, Comp, 47 ohms, <u>+</u> 5%, 1/4 watt	RC07GF470J
R3	Res, Fxd, Comp, 560 ohms, <u>+</u> 5%, 1/4 watt	RC07GF561J
R4	Res, Fxd, Comp, 3900 ohms, <u>+</u> 5%, 1/4 watt	RC07GF392J
R5	Res, Fxd, Comp, 22000 ohms, $\pm$ 5%, 1/4 watt	RC07GF223J

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R6	Res, Fxd, Comp, 1000 ohms, +5%, 1/4 watt	RC07GF102J
R7	Same as R2	
R8	Res, Fxd, Comp, 470 ohms, <u>+</u> 5%, 1/4 watt	RJ07GF471J
R9	Res, Var, Comp, 500 ohms, $\pm 30\%$ , $1/2$ watt	RV124-2-501
R10	Same as R4	
R11	Same as R5	
R12	Same as R6	
R13	Same as R2	
R14	Same as R8	
R15	Same as R4	
R16	Res, Fxd, Comp, 10000 ohms, +5%, 1/4 watt	RCO7GF103J
R17	Same as R6	
R18	Res, Fxd, Comp, 22 ohms, <u>+</u> 5%, 1/4 watt	RC07GF220J
R19	Same as R8	
R20	Res, Fxd, Comp, 47000 ohms, +5%, 1/4 watt	RC07GF473J
R21	Same as R1	
R22	Same as R3	
R23	Same as R2	
R24	Res, Fxd, Comp, 3300 ohms, <u>+</u> 5%, 1/4 watt	RC07GF332J
R25	Same as R5	
R26	Same as R6	
R27	Res, Fxd, Comp, 10 ohms, <u>+</u> 5%, 1/4 watt	RC07GF100J
R28	Same as R3	
R29	Res, Fxd, Comp, 5600 ohms, +5%, 1/4 watt	RC07GF562J

A4647

A.3.2 0702	5. 00.000	PALT TIEER
R30	Res, Fxd, Comp, 6800 ohms, ±5%, 1/4 wast	, NOSTONSSEJ
<b>X</b> 01	Samu as Ró	
R32	Same as R8	
, R33	Same as R29	
704	Same as R16	
R35	Same as Ró	
R36	Same as Ró	
R37	Res, Fxd, Comp, 270 ohms, <u>+</u> 5%, 1/4 watt	R007GT271J
R3S	NOT USED	
R39	Res, Fmd, Comp, 68 ohms, ±5%, 1/4 watt	xc07gr680J
740	Same as RS7	
241	Same as R37	: :
1.42	Same as R5	
<u>145</u>	Same as R4	
Å	Same as kū	:
	Same as A2	
£46	Same as Kô	
	Same at 10	
: <u>1</u> 48	Same as R4	
Z49	Same as 35	
	Same as Ró	
<i>(7)</i>	. Same as k2	
R52	Same as Rő	
53	Same as R4	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R54	Same as R16	
R55	Same as R6	
R56	Same as R18	_
R57	Same as R8	
R58	Same as R20	
R59	NOT USED	
thru		
R62	·	
R63	Res, Fxd, Comp, 560000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF564J
R64	NOT USED	
thru		
R66		
R67	Same as R63	
R68	Res, Fxd, Comp, 1500 ohms, <u>+</u> 5%, 1/4 watt	RC07GF152J
R69	Res, Fxd, Comp, 56 ohms, <u>+</u> 5%, 1/4 watt	RC07GF560J
R70	Same as R27	
R71	Same as R27	
R72	Same as R8	
R73	Same as R8	
<b>Z1</b>	Oscillator, Oven	AO-125(*)
Z2	Oscillator, Oven	AO-125(*)
<b>Z</b> 3	Mixer, Bal	NW163
<b>Z</b> 4	Transformer, RF, Adjustable	TZ-223(**)
<b>Z</b> 5	Transformer, RF, Adjustable	TZ-225(**)
<b>Z</b> 6	Same as Z5	
<b>Z</b> 7	Transformer, RF, Adjustable	TZ-226(**)
Z8	Same as Z4	
<b>Z</b> 9	Same as Z5	
Z10	Same as Z5	
Z11	Same as Z7	
	* Oscillator Frequency ** Type determined by Oscillator Frequency	

# RF OUTPUT A-4502

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
Cl	Capacitor, Fixed, Plastic: 0.82 uf, ±5%, 60 WVDC	CN114R82-5J
C2	Capacitor, Fixed, Electrolytic, 20uf, 50 WVDC	CE105-20-50
C3	Capacitor, Fixed, Ceramic, 10000 uuf, +80-20%, 500 WVDC	CC100-16
C4	Same as C1	
C5 Thru C17	Same as C3	
C18	Capacitor, Fixed, Mica: 620 uuf, $\pm \frac{1}{2}\%$ , 500 WVDC	CM111F621D5S
C19	Capacitor, Fixed, Electrolytic: 50 uf, 50 WVDC	CE105-50-50
C20	Capacitor, Fixed, Mica, 2200 uuf, ±2%, 500 WVDC	CM112F222G5S
C21 thru C30	Not used	
C31	Capacitor, Fixed, Electrolytic, 50 uf, 15 WVDC, or Same as C3	CE105-50-15
C32 th <b>r</b> u	Same as C3	
C34 C35	Capacitor, Fixed, Ceramic: 1,000 uuf, 500 WVDC	CC100-29
C36	Same as C3	
C37	Same as C35	
C38	Same as C3	
C39	Capacitor, Fixed, Mica, 1100 uuf, $\pm \frac{1}{2}\%$ , 500 WVDC	CM112F112G5S
CRl	Semiconductor Device, Diode	IN4864
CR2	Semiconductor Device, Diode	IN100
CR3	Same as CR2	
Ll	Coil, Radio Frequency: 120 uh, ±10%	CL240-120
	<u> </u>	

#### RF OUTPUT A-4502

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
L2 thru L6	Same as Ll	-
L7	Coil, Radio Frequency, 3.90 uh, ±20%	CL240-3R9
L8	Same as Ll	
L9 thru L12	Not Used	·
L13	Coil, Radio Frequency: fixed, 120 uh, ±10%	CL275-121
L14	Same as L1	
L15 thru L22	Same as L13	
L23	Coil, Radio Frequency: fixed, 212 uh, ±10%,	CL275-2R2
L24	Coil, Radio Frequency, 5.60 uh, <u>+</u> 20%	CL240-5R6
Q1	Transistor	2N5070
Q2	Transistor	2N3375
Q3	Transistor	2N3296
R1	Resistor, Variable, Composition: 10,000 ohms, ±30%, 0.5 watts	RV124-1-103
R2	Same as Rl	
R3	Resistor, Fixed, Composition: 22 ohms, ±5%, ½ watt	RC20GF220J
R4	Resistor, Variable, Composition: 5,000 ohms, ±30% ½ watt	RV124-1-502
R5	Resistor, Fixed, Composition: 5600 ohms, ±5%, ½ watt	RC20GF562J
R6	Resistor, Fixed, Composition: 3300 ohms, 5%, 1/2 watt	RC20GF332J
R7	Resistor, Fixed, Composition: 1000 ohms, ±5%, 1 wat	RC32GF102J
R8	Same as R3	

#### RF OUTPUT A-4502

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R9	Resistor, Fixed, Composition: 1000 ohms, ±5%, ½ watt	RC20GF102J
. R10	Not Used	
Rll	Resistor, Fixed, Composition: 47 ohms, ±5%, ¼ watt	RC07GF470J
R12	Same as R9	
R13	Resistor, Fixed, Composition: 10 ohms, ±5%, ½ watt	RC20GF100J
R14	Resistor, Fixed, Composition, 100 ohms, ±5%, 1/2 w	RC20GF101J
R15	Resistor, Fixed, Composition: 2200 ohms, ±5%, ½ watt	RC20GF222J
R16	Not used	
R17	Same as R9	·
R18	Resistor, Fixed, Composition: 220 ohms, ±5%, ½ watt	RC20GF221J
R19	Resistor, Fixed, Composition: 47000 ohms, ±5%, ½ watt	RC20GF473J
R20	Same as R14	
R21	Resistor, Fixed, Composition: 43,000 ohms, ±5%, ½ watt	RC20GF433J
. Tl	Transformer, Radio Frequency: fixed,	TZ220
T2	Transformer, Radio Frequency: fixed,	TZ219

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C301 C302 C303 C304	Cap, Fxd, Cer, 100000 uuf, +80-20%, 300 WVDC Cap, Fxd, 100 mfd, 200 WVDC Cap, Fxd, Elec, 150 mfd, 75 WVDC Cap, Fxd, Mtlz, 47 mfd, +5%, 400 WVDC	CC100-37 CN112A-105M2 CE105-150 CN114R47-5J
C305	Same as C301	
C306	Same as C301	
C307	NOT USED .	
C308	Same as C301	
C309	Cap, Fxd, Elec, 50 mfd, 50 WVDC	CE105-50-50
CR301	Scond, Dev, Dio	1N2484
CR302	Same as CR301	
J301 .	Conn, Recp, ML, 14 contacts, 20 AWG.	JJ242-5P
J302	Conn, Recp, RF, 48 ohms, 500 WVDC, male contact (one contact)	JJ211
J303	Conn, Recp, Fm1, 12 double contacts	JJ319-6DPE
J304	Same as J303	
J305	Same as J302	
J306	Conn, Recp, Fml, 14 contacts, 20 awg	JJ242-5S
L301	Coil, RF, Fxd, 120 uh, 311 ma	CL275-121
P301	Conn, Pl, Fml, 5 contacts,	PL225-8S
R301	Res, Fxd, Comp, 47 ohms, $\pm$ 5%, 1/2 watt	RC20GF470J
R302	Res, Fxd, WW-5W, 15 ohms, 577 ma	RW107-10
T301	XFMR, SD, 115/230 VAC, 50/60 Hz	TF0352
XZ301 and XZ302	Soc, Elec, Tube, 1250 WVDC, 3 amps, 8 contacts	TS100-3
Z301	1 MHz Standard	NF116-1
Z302	Ovenized Oscillator	AO-121
Z303	PC, Bd, B	A-4513
Z304	PC, Bd, A	A-4512

## PC BD A POWER SUPPLY A-4512

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
Cl	Capacitor, Fixed, Electrolytic, 150 mfd, 75 WVDC	CE105-150-75
C2	Capacitor, Fixed, Electrolytic, 200 mfd, 50 WVDC	CE105-200-50
C3	Same as C2	
C4	Same as Cl	
CR1	Rectifier, Semiconductor, Device	DD144-6
	··	
	·	
	·	
		·

### PC BD B POWER SUPPLY A-4513

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
Cl	Capacitor, Fixed Electrolytic, 25 mfd, +50-15%, 50 WVDC	CE107-6
C2	Same as Cl	-
C3	Same as Cl	
C4	Same as Cl	
C5	Same as Cl	
CR1	Semiconductor, Device Diode	1N100
CR2	Same as CR1	
CR3	Semiconductor, Device, Diode	lN4619
CR4	Semiconductor, Device, Diode	1N753A
CR5	Same as CR3	
CR6	Semiconductor, Device, Diode	1N972B
CR7	Same as CR4	
Ql	Transistor	2N1481
Q2	Same as Ql	
QЗ	Same as Q1	
Q4	Transistor	2N3638
Q5	Same as Q1	
Q6	Same as Q4	
Q <b>7</b>	Same as Q1	
Rl	Resistor, Fixed, Composition, 470 ohms, ±5%, ¼ watt	RC07GF471J
R2	Resistor, Fixed, Composition, 1000 ohms, ±5%, \u00e4watt	RC07GF102J
R3	Resistor, Variable, Composition, 1000 ohms, ±30%, watt	RV124-1-102
R4	Same as R2	
R5	Same as R2	

### PC BD B POWER SUPPLY A-4513

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R6	Resistor, Fixed, Composition, 10000 ohms, ±5%, \watt	RC07GF103J
R7	Same as R2	-
R8	Same as R3	
R9	Resistor, Fixed, Composition, 4700 ohms, ±5%, \( \frac{1}{4}\)watt	RC07GF472J
R10	Resistor, Fixed, Composition, 1500 ohms, ±5%, \u224watt	RC07GF152J
Rll	Resistor, Fixed, Wirewound, 1 ohms, ±2%, 5 watt	RR114-1.0W
R12	Same as R3	
R13	Resistor, Fixed, Composition, 6800 ohms, ±5%, \u00e4watt	RC07GF682J
R14 ,	Same as R2	
R15	NOT USED	
R16	Same as R9	•
R17	Resistor, Fixed, Composition, 150 ohms, ±5%, \( \frac{1}{4}\) watt	RC07GF151J
R18	Resistor, Variable, Composition, 10000 ohms, ±30%, ½ watt	RV124-1-103
R19	Same as R17	
	·	
	·	
•	·	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C1	Cap, Disc, Cer, 100000 uuf, +80-20%, 25 WVDC	CC100-44
C2	Cap, Fxd, Mica, 22 uuf, <u>+</u> 5%, 500 WVDC	CM111C220J5S
C3	Cap, Disc, Cer, 10000 uuf, <u>+</u> 20%, 50 WVDC	CC100-42
C4	Cap, Elec, 10 mfd, +75-15%, 25 WVDC	CE122-10-25
C5	Same as C3	
C6	Same as C4	·
C7	Cap, Fxd, Elec, 6.8 mfd, 25 WVDC	CE122-6R8-25
C8	Same as C3	
С9	Same as C4	
C10	Same as C7	
C11	Same as C4	
C12 C13 thru C14 C15 C16 C17 C18 C19 C20 C21 and C22 C23	Cap, Fxd, Elec, 22 mfd, 16 WVDC Same as C7  Same as C1 NOT USED Same as C12 NOT USED NOT USED Same as C1 Same as C1 Same as C1 Same as C1	CE122-22-16
thru C27 C28	Cap, Fxd, Mica, 3900 uuf, +2%, 300 WVDC	CM112F392G3S

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C29 thru C32	Same as Cl	
C33	Same as C28	
C34 thru C36	Same as Cl	·
C37	Cap, Var, Cer, 9-35 uuf, 100 WVDC	CV112-8
C38	Same as C7	
C39	Same as Cl2	
C40 .	Same as C1	
C41	Cap, Disc, Cer, 100000 uuf, +80-20%, 100 WVDC	CC100-28
C42	Same as C41	
C43	Same as Cl	
C44	Same as Cl	
C45	Same as C12	
C46 thru C48	Same as Cl	
C49	Same as C41	
C50	Same as Cl	
C51	Same as Cl	
C52	Cap, Fxd, Mica, 10000 uuf, <u>+</u> 5%, 100 WVDC	CM112F103J1S
C53 and C54	Same as C41	
C55 and C56	Same as Cl	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C57	Same as C41	·
C58	Same as Cl	
C59	Same as C41	
C60	Same as C41	
C61	Same as C7	
C62	Same as C7	
C63 and C64	Same as C12	
C65	Same as C7	
C66	Same as C12	
C67	Cap, Fxd, Mica, 300 uuf, <u>+</u> 5%, 500 WVDC	CM111F301J5S
C68	Same as C7	
C69	Cap, Fxd, Elec, 6.8 mfd, 35 WVDC	CE122-6R8-35
C70	Same as C69	
C71	Same as C4	
C72	Same as C7	
C73 C74 C75 C76 C77 C78 C79 C80 C81	Same as C7 Same as C41 Same as C41 Same as C12 Same as C3 NOT USED NOT USED Same as C7 Same as C7	
CR1	Diode, Silicon	1N914
CR2	Same as CR1	
CR3 CR4	Same as CR1 Diode, Ref, Silicon	1N961
	2220, 101, 0111011	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
CR5 and CR6	Same as CR1	
CR7	Diode,	1N4245
K1	Relay, Armature, Min	RL143-4
L1 thru L3 L4 L5 thru	Cc.1, 1000 uh, <u>+</u> 10%, 135 ma  NOT USED  Same as L1	CL275-102
L10 L11 L12 thru L17	NOT USED Same as L1	
Q1 thru Q7	Transistor, Silicon	2N3646
Q8	Transistor, GE	2N1225
Q9 and Q10	Transistor, Silicon	2N863
Q11	Same as Q8	
Q12	Same as Q8	
Q13	Same as Q9	
Q14 thru Q16	Same as Q9	
Q17 and Q18	Same as Q1	
Q19	Same as Q8	
Q20	Same as Q1	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
Q21 thru Q26	Same as Q1	
Q27	Transistor	2N696
Q28	Same as Q1	
Q29	Same as Q1	·
R1	Res, Fxd, Comp, 1200 ohms, <u>+</u> 5%, 1/4 watt	RC07GF122J
R2	Res, Fxd, Comp, 47000 ohms, ±5%, 1/4 watt	RC07GF473J
R3 -	Res, Fxd, Comp, 10000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF103J
R4	Res, Fxd, Comp, 56000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF563J
R5	Res, Fxd, Comp, 100000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF104J
R6	Same as R4	
R7	Res, Fxd, Comp, 470000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF474J
R8	Res, Var, 5000 ohms, +5%	RV124-1-502
R9	Same as R3	
R10	Res, Fxd, Comp, 22000 ohms, +5%, 1/4 watt	RC07GF223J
R11	Res, Fxd, Comp, 1500 ohms, +5%, 1/4 watt	RC07GF152J
R12	Res, Fxd, Comp, 100 ohms, <u>+</u> 5%, 1/4 watt	RC07GF101J
R13	Res, Fxd, Comp, 470 ohms, +5%, 1/4 watt	RC07GF471J
R14	Same as R10	
R15	Same as R3	
R16	Same as R13	
R17	Same as R12	
KĪ 8	Same as R11	
R19	Same as R2	

REF		
SYMBOL	DESCRIPTION	TMC PART NUMBER
R20	Res, Fxd, Comp,1500 ohms, <u>+</u> 5%, 1/4 watt	RC07GF153J
R21	Res, Fxd, Comp, 1000 ohms, <u>+5</u> %, 1/4 watt	RC07GF102J
R22	Res, Fxd, Comp, 5600 ohms, +5%, 1/4 watt	RC07GF562J
R23	Same as R22	
R24	Res, Fxd, Comp, 270 ohms, <u>+</u> 5%, 1/4 watt	RC07GF271J
R25	Res, Fxd, Comp, 47 ohms, $\pm 5\%$ , 1/4 watt	RC07GF470J
R26	Res, Fxd, Comp, 330 ohms, <u>+</u> 5%, 1/4 watt	RC07GF331J
R27	Same as R21	
R28 .	Same as R21	
R29	Res, Fxd, Comp, 22 ohms, +5%, 1/4 watt	RC07GF220J
R30	Res, Fxd, Comp, 3300 ohms, <u>+</u> 5%, 1/4 watt	RC07GF332J
R31	Same as R24	
R32	Same as R24	
R33	Same as R30	
R34	Same as R29	
R35	Same as R21	
R36	Same as R30	
R37	Same as R3	
R38	Same as R3	
R39	Res, Fxd, Comp, 680 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF681J
R40	Res, Fxd, Comp, 8200 ohms, <u>+</u> 5%, 1/4 watt	RC07GF822J
R41	Res, Fxd, Comp, 390 ohms, <u>+</u> 5%, 1/4 watt	RC07GF391J
R42	Same as R30	
R43	Same as R25	

RE F SYMBOL	DESCRIPTION	TMC PART NUMBER
R44	Same as R5	
R45	Res, Fxd, Comp, 330000 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF334J
R46	Same as R22	
R47	Same as R12	
R48	Res, Fxd, Comp, 6800 ohms, +5%, 1/4 watt	RC07GF682J
R49	Same as R3	
R50	Same as R48	
R51	Same as R21	
R52	NOT USED	
R53	Res, Fxd, Comp, 2200 ohms, <u>+</u> 5%, 1/4 watt	RC07GF222J
R54	Same as R25	
R55	Res, Fxd, Comp, 4700 ohms, <u>+</u> 5%, 1/4 watt	RC07GF472J
R56	Same as R8	
R57	Same as R53	
R58	Same as R12	
R59	Same as R25	
R60	Res, Fxd, Comp, 820 ohms, +5%, 1/4 watt	RCO7GF821J
R61	Res, Fxd, Comp, 150000 ohms, +5%, 1/4 watt	RC07GF154J
R62	Same as R53	
R63	Same as R3	
R64	Res, Fxd, Comp, 180 ohms, +5%, 1/4 watt	RC07GF181J
R65	Same as R29	
R66	Same as R21	
R67	Same as R53	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R68	Same as R22	· ·
R69	Same as R22	
R70	Same as R1	
R71	Same as R11	
R72	Same as R21	
R73	Same as R22	.
R74	Same as R10	
R75	Same as R40	
R76	Same as R25	
R77	Same as R20	
R78	Res, Fxd, Comp, 3900 ohms, <u>+</u> 5%, 1/4 watt	RC07GF392J
R79	Same as R21	
R80	Res, Fxd, Comp, 10 ohms, <u>+</u> 5%, 1/4 watt	RC07GF100J
R81	Same as R13	
R82	Same as R22	
R83	Same as R10	
R84	Same as R21	
R85	Same as R24	
R86	Same as R12	
R87	Res, Fxd, Comp. 220000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF224J
R88	Same as R53	
R89	Same as R78	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R90	Same as R20	,
R91	Same as R21	
R92	Res, Fxd, Comp, 56 ohms, <u>+</u> 5%, 1/4 watt	RC07GF560J
R93	Same as R21	
R94	Same as R1	
R95	Same as R64	
T1	Transformer, Audio, Matching	TF359 ·
T2	Transformer, RF, Tuned	TT285-11
Т3	Same as T2	
Т4	Transformer, RF Tuned	TT286-7
Y1 \( \cdot \)	Crystal, Quartz	CR109-147
Z1	BAL. MOD.	NW163
Z2 <b>*</b>	Filter, Bandpass; 250 kHz, Upper Sideband	FX195-4
	Filter, Bandpass; 250 kHz, Lower Sideband	FX195-5
	* - Particular filter supplied depends upon option specified. A4707 plus FX195-4 becomes A4707-1, which is the Upper Sideband option; A4707 plus FX195-5 becomes A4707-2, or the Lower Sideband option. When ISB option is specified, two A4707 boards are supplied; one containing FX195-4, and the other containing FX195-5, thus providing both A4707-1 and A4707-2, to permit operation on either or both sidebands independently and simultaneously.	

REF SYMBOL	DESCRIPTION	TMC
C1	Cap, Fxd, Elec, 125 ufd, 15 WVDC	PART NUMBER
C2	Cap, Fxd, Elec, 10 ufd, 25 WVDC	CE105-125-15
C3		CE105-10-25
	Cap, Fxd, Cer, 100000 PF, +80-20%, 25 WVDC	CC100-44
C4	Cap, Fxd, Elec, 25 ufd, 25 WVDC	CE105-25-25
C5	Cap, Fxd, Cer, 10,000 uuf, +80-20%	CC100-41 ·
C6	Cap, Fxd, Elec, 10 ufd, 25 WVDC	CE105-10-25
C7	Cap, Fxd, Elec, 40 ufd, 15 WVDC	CE105-40-15
С8	Same as C3	
С9	Cap, Fxd, Elec, 100 ufd, 15 WVDC	CE105-100-15
C10	Cap, Fxd, Mica, 3900 PF, +1%, 300 WVDC	CM112F392G3
C11	Same as C3	
C12	Cap, Fxd, Cer, 200000 uuf, +80-20%, 25 WVDC	CC100-33
Ll	Coil RF, 330 uh, +10%, 215 ma.	CL275-331
L2	Coil RF, 220 uh, +10%, 250 ma.	CL275-221
L3	coil RF, 1000 uh, <u>+</u> 10%, 135 ma.	CL275-102
Rl	Res, Fxd, Comp, 3300 ohms, $\pm$ 5%, 1/4 watt	RC07GF332J
R2	Res, Fxd, Comp, 10000 ohms, $\pm$ 5%, 1/4 watt	RC07GF103J
R3	Res, Fxd, Comp, 1500 ohms, $\pm$ 5%, 1/4 watt	RC07GF152J
R4	Res, Fxd, Comp, 18 ohms, <u>+</u> 5%, 1/4 watt	RC07GF180J
R5	Res, Fxd, Comp, 470 ohms, $\pm$ 5%, 1/4 watt	RC07GF471J
R6	Res, Fxd, Comp, 270 ohms, $\pm$ 5%, 1/4 watt	RC07GF271J
R7	Res, Fxd, Comp, 1000 ohms, $\pm$ 5%, 1/4 watt	RC07GF102J
R8	Same as R5	
R9	Same as R2	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R10	Res, Fxd, Comp, 47000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF473J
R11	Res, Fxd, Comp, 100 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF101J
R12	Same as R5	
R13	Res, Fxd, Comp, 47 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF470J
R14	Same as R5	
R15	Res, Var, Comp, 100 ohms, + 30, 1/2 watt	RV124-1-101
T1	Transformer RF Tuned	TT285-15
Q1	Transistor,	2N3646
Q2	Same as Q1	·
Q3	Same as Q1	
	·	
	•	

REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C1 thru C4	Cap, Disk, Cer, 10000 uuf, +80%-20%	CC100-41
C5	Cap, Disk, Cer, 20000 uuf, +80%-20%, 25 WVDC	CC100-40
C6	Same as C1	
C7	Cap, Mica, Fxd, 5 uuf, +10%, 500 WVDC	CM111C050K5S
C8	Same as C5	
C9	Same as Cl	
C10	Same as Cl	
C11	Cap, Disk, Cer, 200000 uuf, +80%-20%, 25 WVDC	CC100-33
C12	NOT USED	
C13	Cap, Disk, Cer, 1000 uuf, +80%-20%,	CC100-29
C14	Same as C13	
C15	Cap, Mica, Fxd, 100000 uuf, +80%-20%, 25 WVDC	CC100-44
C16	Same as C13	
CR1	Semiconductor, Diode	1N914
CR2	Same as CR1	
CR3	Semiconductor, Diode, Silicon	1N34A
CR4 thru CR6	Same as CR3	
CR7 and CR8	Semiconductor, Diode, Silicon	1N755A
CR9 thru CR13	Semiconductor, Diode, Silicon	1N627
CR14	Semiconductor, Diode, Silicon	1N752A


REF SYMBOL	DESCRIPTION	TMC PART NUMBER
L1	Coil, 1000 UH, <u>+</u> 10%, 135 MA	CL275-102
L2	Coil, 220 UH, +10%, 250 MA	CL275-221
Q1 and Q2	Transistor, Silicon	2N3646
Q3	Transistor, Silicon	2N1711 ·
Q4 thru Q8	Transistor, Silicon	2N696
Q9 .	Same as Q3	
R1	Res, Fxd, Comp, 6800 ohms, <u>+</u> 5%, 1/4 watt	RC07GF682J
R2	Res, Fxd, Comp, 2200 ohms, <u>+</u> 5%, 1/4 watt	RC07GF222J
R3	Res, Fxd, Comp, 470 ohms, +5%, 1/4 watt	RC07GF471J
R4	Res, Fxd, Comp, 1500 ohms, +5%, 1/4 watt	RC07GF152J
R5	Res, Fxd, Comp, 1000 ohms, +5%, 1/4 watt	RC07GF102J
R6	Res, Fxd, Comp, 10000 ohms, +5%, 1/4 watt	RC07GF103J
R7	Same as R2	
R8	Same as R5	
R9	Res, Fxd, Comp, 4700 ohms, +5%, 1/4 watt	RC07GF472J
R10	Res, Fxd, Comp, 22000 ohms, +5%, 1/4 watt	RC07GF223J
R11	Same as R6	
R12	Same as R10	
R13	Same as R10	
R14	Same as R3	
R15	Same as R9	
R16	Res, Var, 1000 ohms, <u>+</u> 30%	RV124-1-102


#### A-4905


REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R17 thru R20	Res, Fxd, Comp, 47000 ohms, +5%, 1/4 watt	RC07GF473J
R21	Same as R1	
R22	Same as R1	
R23	Res, Var, 10000 ohms, +5%,	RV119-2-103D
R24	Same as R17	
R25	Same as R23	
R26	Same as R6	
R27	Res, Fxd, Comp, 220 ohms, <u>+</u> 5%, 1/4 watt	RC07GF221J
R28	Same as R1	
R29	Same as R23	
R30	Same as R6	
R31	Res, Fxd, Comp, 100000 ohms, +5%, 1/4 watt	RCO7GF104J
R32	Same as R6	
R33	Res, Fxd, Comp, 330 ohms, +5%, 1/4 watt	RC07GF331J
R34	Same as R5	
T1	Transformer, 795 KHz, "Q" 710, "L" +20%, 250 UH	TZ216
T2	Transformer, 795 Kc/S, "Q" 710, "L" ±20%, 250 UH	TZ218
<b>Z1</b>	Network Int., Ckt., 3.0 WVDC, +10%	NW137


REF SYMBOL	DESCRIPTION	TMC PART NUMBER
C1	NOT USED	
thru		
C16		
C17	Cap, Disk, Cer, 10000 uuf, +80%-20%	CC100-41
C18	Cap, Fxd, Mica, 110 uuf, $\pm 2\%$ , 500 WVDC	CM111F111G5
C19	Same as C17	Oritite 111G)
C20	Cap, Var, 8-50 uuf, 350 WVDC	CV109-9
C21	Cap, Fxd, Mica, 220 uuf, +5%, 500 WVDC	
C22	Same as C17	CM111F221G5
C23	Same as C17	
C24	Cap, Fxd, Cer, 1000 uuf, +80%-20%	CC100-29
C25	Same as C24	CC100=29
C26	Same as C17	
C27	Cap, Fxd, Mica, 100 uuf, +2%, 500 WVDC	W1117101056
C28	Cap, Fxd, Mica, 200 uuf, +2%, 500 WVDC	CM111F101G59
C29	Same as C27	CM111F201G55
CR1	NOT USED	
thru		
CR14		
CR15	Diode, Semiconductor, Device	1W061p
L1	NOT USED	1N961B
L2	NOT USED	
L3	Coil, RF, 220 uh, <u>+</u> 10%, 250 ma	GI 275 007
L4	Same as L3	CL275-221
Q1	NOT USED	
thru		
Q9		
Q10	Transistor, Silicon	2372676
thru	,	2N3646
Q12		
R1	NOT USED	
thru	•	
R34		


REF SYMBOL	DESCRIPTION	TMC PART NUMBER
R35	Res, Fxd, Comp, 100 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF102J
R36	Res, Fxd, Comp, 2200 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF222J
R37	Res, Fxd, Comp, 68000 ohms, +5%, 1/4 watt	RCO7GF683J
R38	Res, Fxd, Comp, 18000 ohms, <u>+</u> 5%, 1/4 watt	RC07GF183J
R39	Res, Fxd, Comp, 3300 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF332J
R40	Same as R35	
R41	Same as R35	
R42	Res, Fxd, Comp, 1500 ohms, <u>+</u> 5%, 1/4 watt	RC07GF152J
R43	Res, Fxd, Comp, 22000 ohms, $\pm 5\%$ , $1/4$ watt	RC07GF223J
R44	Res, Fxd, Comp, 4700 ohms, <u>+</u> 5%, 1/4 watt	RCO7GF472J
R45	Same as R42	
R46	Same as R35	
Y1	Crystal, Quartz	CR18/AU- 4.416667 MHz














SHEET 2


EN PLEASURE NAME OF THE PARTY. XI PEVISED & UPDATED


O CRIGINAL RELETISE FOR PEDDUCTION 12/10/68 RG 12.27.6 8-4-69 19526 KD REVISED & UPDATED C162 WAS C110 (DUPLICATION)











	HE STATE HAVE WELL	Per la
	- OTESTS	
3	17.07.03	
1		
*	TO SOLD TO SOLD OF	
	Live 11-7-62	
	DRAWN SEE SEE	. SME-6.
-1		

RECURSON PART NO.


SECTION S


Figure 7-1.


SME-6. Interconnecting Diagram


(Sheet 1 of 2)

7-3/7-4









1.10	A STATE OF THE STA	A STATE OF THE PROPERTY OF THE				STREET, STREET
		KEVISED & CUPINITED	41400		X.	
<i>\$</i> ^-	Ø	ORIGINAL RELEASE FOR PRODUCTION	4.27.68		RE	
		REVISED & UPDATED	8-4-69	19526	KO	44/OP
	B	RIZO VAL. W/5.9K LIII & LIIBW/ 1-0	9/2/12	20889	SE	El CD


100	SERIES.
LAST SYMBOLS	MISSING SYMBOLS
C162	
DS102	
F102	
J 125	J108, J110, J122
L118	L110, L112, L115
M101	
R147	
\$111	S107, S108
TB105	TB101,TB102
Z115	Z106, Z110
K102 CR102	JII4 ZII4


300	SERIES
LAST SYMBOLS	MISSING SYMBOLS
P306	P3031, P304


## UNLESS OTHERWISE SPECIFIED:


- 1 ALL RESISTORS ARE IN OHMS.
- 2. ALL CAPACITOR VALUES ARE IN MICROFARADS
- 3. ALL INDUCTANCE VALUES ARE IN MICROHENRIES.

OUT
MISSING NUMBER
11,44,57










100	SERIES.
LAST SYMBOLS	MISSING SYMBOLS
C162	
DS102	
F102	
J 125	J106, J110, J122
L118	L110, L112, L115
M101	
R147	
S111	\$107,\$108
TB105	TB101,TB102
Z115	Z106,Z110
K102 CR102	JII4 ZII4

300	SERIES
LAST SYMBOLS	MISSING SYMBOLS
P306	P303, P304

## UNLESS OTHERWISE SPECIFIED:

- 1 ALL RESISTORS ARE IN OHMS.
- 2. ALL CAPACITOR VALUES ARE IN MICROFARADS
- 3. ALL INDUCTANCE VALUES ARE IN MICROHENRIES.

BREAK	OUT	
LAST NUMBER	MISSING NUMBER	
<b>6</b> 6	11,44,57	




17


50

Figure 7-1.


SME-6. Interconnecting Diagram

(Sheet 2 of 2)





7-21/7-22



TOTAL SHEETS

OP. COLIMINARY

MATERIAL T TO

[]FIMAL

FOR

TMC MODEL - SME( )-6

REV.

SHEET (S)

DATE

APPR.

REVISION

TITLE-SIDEBAND MULTI-CHANNEL EXCITER

MODEL -USED ON

SUPPORTING LISTS CONSISTS OF

A-4707-1 A-4707-2 A-4647

A-4718 AX5039 BMA478

LAST SYMBOLS Z113Z103,104,106,107 Z110

SYMBOLS NOT USED

CHROKED COUNTY STATE

ENG APPR ES DATE FNL APPR 121/12

ENGINERNING JOB NUMBER

 $\infty$ FOR SPECIAL NOTES, REFER TO \$1200.

£

## 

SME()-6 REV.

PAGE I OF

PART NUMBER	DESCRIPTION	USED ON	QTY.	OTY. PER UNIT	REFERENCE SYMBOLS	SPECIAL NOTES REFER TO S 1200
A-4647	R.F. AMP	SME ( ) -6 SME ( ) -6 SME ( ) -6 SME ( ) -6 SME ( ) -6		*	Z101 Z102 Z111 Z112 Z113	1, 111 1, 111 1, 111 1, 111 1, 111
A-4707-1	USB GEN	SME()-6 SME()-6	Book is specially the top	* H	Z105	O .
A-4707-2	LSB GEN	SME ( ) -6 SME ( ) -6	p	* ~!	2109	55 0
A-4718	ALI AMP	SME ( ) -6 SME ( ) -6	p{	*	2108	50 50
AX5039	DASIC EXC ASSY	SME()-6	r-1	*		r-1
BMA305	FSK-FAX ASSY	SME ( ) -6 SME ( ) -6		*		1 50, 114
DMA478	FSK-FAX ASSY	SME ( )-6 SME ( )-6		* H		50 50
CA1151-7	CEL, ASSY, PWR	SME()-6	p	*		7
CK1490	SCHEMATIC DIAG	SME()-6	r-l	* H		
			Constitution of the state of th			